dev
Consultant Engineer & Interior Designing
B/501/2, Tirupati Plaza, Near Collector Office, Nanpura, Surat-395001 Gujarat, India.
Mo. : (o) +91-99099-06885
Email .: devarch19@ gmail.com.

Name Of Work : Total Interior Work of Bank Building @ Rander Branch, Dist Surat.

Name Of Owner : The Surat District Co-Operative Bank, majura gate, Surat.

TOTAL ESTIMATE OF INTERIOR WORK

Sr.No	Description	Area (sq.ft.)	Amount (INR)
1	FURNITURE WORK (A)		
2	ATM ROOM + ELECTRIC (B)		
3	ELECTRIC WORK		
4	Air Condition Required system (Office +ATM)		
	TOTAL		
	GRAND TOTAL	SAY	

NOTE

*	If any other work Required not including in drawing or estimatd cost are solve in on required or Discussion at site level.		
*	All lum-sum Amount are not consider say amount so at the time of we invite Estimate cost from relected contactor or wender.		
*	Not consider locker main door,strong room door, lockers & safe.		
*	All Matarials & it's colours as aproved by consultant architect.		

For,
dev

Consultant Engineer and Interior Designing

dev
Consultant Engineer & Interior Designing
B/501/2, Tirupati Plaza, Near Collector Office, Nanpura, Surat-395001 Gujarat, India.
Mo. : (o) +91-99099-06885
Email .: devarch19@ gmail.com.
Name Of Work : Furniture Work of Surat District co.op. bank ltd. @ Rander branch,Dist.Surat.
Name Of Owner : The Surat District Co-Operative Bank, majura gate, Surat.

OFFICE FURNITURE WORK

(A)

Sr.No	Description	Qty	Per	Rate	Amount
1	Table for All Department				
(a)	Staff Main Table				
	Providing and making Staff table for All Department.Table top & sides to be in 19 mm thk comm.ply with 1.0mm thk Laminate finish.Drawers & shutters be made in 12 mm thk com ply with 6 mm ply backing with chanels & finished externally in 1.0 mm thk laminate finish. All internal surface in oil paint /french polish finish. All exposed edges & drawer with T.W or Burma Border lipping patti in melamine polish. The above item includes all necessary hardware like locks, handles,ball catch etc. complete as per detail drawing & design. Rates to include all basic H.W.,brass , fixtures, handles,keyboard of EBCO make & required hardware.All as per detail Architectural drawing & instruction complete. Basic Price of Laminate :- Rs 50/ sq.ft.				
	Size:- 7'-0" (L) X 2'-0" (D) X 4'-0" (H) x 1 nos. (staff)	52.5	sq.ft.		
	Size:- 4'-6" (L) X 2'-0" (D) X 2'-6" (H) x 1nos.(F.L.C.+clearing)	22.5	sq.ft.		
	Size:- 4'-0" (L) X 2'-0" (D) X 2'-6" (H) x 1nos.(Server+U.P.S.)	20	sq.ft.		
(b)	Side Credenza for Staff table				
	Providing and making side credenza 1'-1½" wide. Table top & sides to be in 19 mm thk comm.ply with 1.0mm thk Laminate finish Shutter in 19mm thk com ply with 1.0 mm thk lamiante finish.The above item includes all necessary hardware like locks, handles,hinges etc. approved 1.0 mm thk laminate .All as per detail drawing & instruction complete. Basic Price of Laminate :- Rs 50/ sq.ft.				
	Size:- 4'-9" (L) X 1'-1½" (D) X 2'-0" (H) x nos.1(clearing)	11.87	sq.ft.		
	Size:- 4'-9" (L) X 1'-1½" (D) X 2'-0" (H) x nos.1(clearing)	11.87	sq.ft.		
2	Manager Cabin				
(a)	Main Table				
	Providing and making Staff table for A.G.M.cabin.Table top & side to be in 19 mm thk comm.ply with 1.0mm thk Laminate finish. Drawers & shutters tobe made in 12mm thk com ply with 6mm ply backing with chanels & finished externally in1.0mm thk laminate finish.All finished externally in 1.0 mm thk laminate finish.All internal surface in oil paint /french polish finish. All exposed edges of drawer with T.W or Burma Border lipping patti in melamine polish. 19 mm thk com ply shutter in 1.0 mm thk lamiante finish .The above item includes all necessary hardware like locks, handles & hinges ,ball catch etc.complete as per detail drawing & design.Rates to include all basic H.W.,brass hingis, fixtures, handles, keyboard of EBCO make & requires hardware. All as per detail Architectural drawing & instruction complete.				
	Basic Price of Laminate :- Rs 50/ sq.ft.				
	Size:- 5'-6" (L) X 2'-3" (D) X 2'-6" (H) x 1nos.	30.94	sq.ft.		

(b)	Side Credenza for main table			
	Providing and making side credenza 1'-1½" wide.Table top & sides to be in 19 mm thik.comm.ply with 1.0mm thik.Laminate finish shutter in 19mm thik.com.ply with 1.0mm thik. Laminates finished. The above item includes all necessary hardware like locks, handles ,hinges etc. complete 3" hight Skirting to be made in 12 mm thik.com. Ply in appro.1.0 mm thik.laminate.All as per detail drg.& instruction complete.			
	Basic Price of Laminate :- Rs 50/ sq.ft.			
	Size:- 5'-3" (L) X 1'-1½" (D) X 2'-0" (H) x 1nos.	13.12	sq.ft.	
3	Partition			
(a)	Providing & making Half partition in 8mm thk comm.ply both side with			
	1.0mm thk laminate finish both side with necessary alum. pipe size 50 x 25 mm @ 600mm c/c in both direction with 5'-0" ht.(3'-6" solid + 1'-6" glass) with 12mm plain glass with S.S. stude Supports per Architect drawing .			
	Basic Price of Laminate :- Rs 50/ sq.ft.(5'6")	65	sq.ft.	
4	CupBoard			
	Providing and making Cupboad. Table top & sides to be in 19 mm thik. comm.ply with 1.0mm thk Laminate finish Shutter in 19 mm thk.com. ply with 1.0 mm thk lamiante finish. All internal surface to be finished in Oil paint. The above item includes all necessary hardware like locks, handles ,hinges etc. complete.3" high Skirting tobe made in 12 mm thk comm. ply in approved 1.0 mm thk laminate. All as per detail drawing & instruction complete.			
	Basic Price of Laminate :- Rs 50/ sq.ft.			
	Size:- 3'-6" (L) X 1'-3"(D) X 9'-0" (H) X 1nos.(maneger)	40	sq.ft.	
	Size:- 4'-6" (L) X 1'-3"(D) X 9'-0" (H) X 1nos.(near 1 no.table)	51	sq.ft.	
5	FOOTREST			
	Providing and making footrest on each table neseccery hardware as per			
	architural drawing detail. finish with oil paint or french polish with teak			
	wood lipping.			
	Size:- 2'-6" (L) X 0'-9" (D) X 0'-3" (H)	4	nos.	
6	DOOR			
a	DOOR WITH GLASS (FLUSH DOOR)			
	water proof 35mm flush door, make Century or Equilent with both the sides 1.00 mm thik. laminate approved design / approved shade, with Mortise lock, door closer,door stopper,& hinges,all the exposed wooden edges to be finished with approved shade of oil paints or melamine polish.(with all necessary hardware items)			
	Size:- 2'-6" (L) x 7'-0" (H) x 3 nos. (toilet+pentry+store)	0	sq.ft.	
b	DOOR WITHOUT GLASS (FLUSH DOOR)			
	water proof 35mm flush door, make Century or Equilent with both the sides 1.00 mm thik. laminate approved design / approved shade, with Mortise lock, door closer,door stopper,& hinges,all the exposed wooden edges to be finished with approved shade of oil paints or melamine polish.(with all necessary hardware items)			
	Size:- 2'-6" (L) x 7'-0" (H) x 1 nos. (toilet+pentry+store)	17.5	sq.ft.	
7	MAIN ENTERY DOOR & ALL FRONT GLASS			
	Providing 12mm thik.Clear thoughen glass door with making holes / cut-outs as required ,making edges clear smooth polished.approved quality, fixes with good quality glass door rail (SS brush finish or alumini.matt finish) the shutter being held open at 90 degrees angles adjustable closing speed valve,with pivot to suit patch fittings & door shutters.			
	Size:- 4'-0" (L) X 8'-0" (H) door	1	nos	
	Size:-22'-6" (L) X 8'-0" (H) fix glass	185	sq.ft.	

8	GYPSUM FALSE CEILING				
	Supply & fix the Gypsum Ceiling (perforated /venily) as per the drawing attechd here with, /Gypsum heavy gauge G.I. channels or equilant company) suspended approx.2'-6" down from the existing slab (where ever applicable) , all the joints of the Gypsum Sheet tobe finished with jointing compound of the company & the tape as well,all complete without painting.all the Vertical suspensions tobe suspended fixed to the slab with "Anchor Fastrners" and not the normal screws.(bank)	1067	sq.ft.		
9	COLOUR WORK				
a	WALL COLOUR				
	providing & application of painting as required.the paint work shall comprise of applying primer,req.coats of 'lapi'after scraping the old colour and finishing with three coats luster paints or valvet touch paints or equivalent. the colour workshall (matt luster)be on ceiling / walls, all exposed slab,windows and grills.any cracked undulated surface to be filled with cement and pop before lapi work,up the satisfaction of consultant /designer.	3350	sq.ft.		
b	CEILING COLOUR (toilet+ pentry+ store+cash room + locker room)	2290	sq.ft.		
10	P.O.P ON WALL (gypsum powder)				
	providing plaster of paris (Gypsum powder)on wall ½" or 1" to perfect plumb as per site condition after repairing the cracks if any on the wall, electrical jarries to make surface for smooth colour work. Complete with all aspect up the satisfaction of consultant /designer	1250	sq.ft.		
11	chair				
	supplying good quality Chairs with folling specification low back,medium back & high back syncro tilt hight adjustment solved by gas mechanism of suspa or equilant unbreakable twin wheel glass filled nylon casters perfect 360 degree seamless tubular revolving steam (VAT EXTRA)				
	pvc / pu handles				
a	high back chair (manager)	0	nos		
b	midd back chair (loan+clearing+FLC)	2	nos		
c	low back chair (staff + cashier+ visitor+u.g.staff)	4	nos		
12	2 SEATER FIX SITTING				
	Providing & making of 2 seater in hardwood frame of 50 X 38 mm as per support required with 75 mm thk 40 density U foam for the seat and 50mm thk. 40 density U foam for the back with necessary chair, M.S.springs for finished with white cotton cloth and final finished with softness,with composite leather as per pattern design.Sofa will have S.S legs as per design. Basic price of composite leather :- Rs 500 /mt.				
	Size:- 1200 (L) X 750 (D) X 750 (H)	1	nos		
13	Square / Round Side table				
	Providing & making of the designer square side table.Table top in 12 mm thick toughened clear glass with wooden base.Wooden base in melamine polish finish.(VAT EXTRA)				
	Size:- 1'-3" (L) X 1'-6" (D) X 1'-3" (H)	0	0		
14	ENTERANCE DASK				
	Providing & making of the enterance desk with finish work as per Architect detail drawings.				
	Size:- 4'-10" (L) X 0'-9" (D) X 3'-0" (H)	1	nos		

15	COLUMN PANELLING				
	Cladding central column in the banking hall of the ground floor & with 12				
	mm thick water proof plywood with wooden s,exposed surface to be treated				
	treated 1 mm thick approved laminate pasted with approved adhesive,				
	all with. Up to full height only,with end bidding complete.	155.5	sq.ft.		
16	MISCELLENEOUS WORK				
1	Pro.& Fix.box type sign board Latters for main entery side,size	146	sq.ft.		
2	making & fixing ms battery stand for branch	0	nos.		
3	making & fixing venyle display 8mm with sandwich glass	4.5	sq.ft.		
4	pro.& fix bathroom mirror	0	nos.		
5	pro.& fix ss towel ring	0	nos.		
6	Pro.& Fix.wooden writing desk	2	sq.ft.		
7	making & fix venyle bank logo on glass	1	nos.		
8	making & fix table top glass 8mm with holes etc.	0	sq.ft.		
9	Curtain Roller or One Way Vison Screen(film)	0	sq.ft.		
10	Kitchen Shutter (Size:- 5'-0" (L) X 2'-6: (H))	0	sq.ft.		
11	Locker mirror	10	sq.ft.		
12	Venyle Name Plate	0	Nos.		
13	PVC logo on main Entery	18	sq.ft.		
14	Wall clock	0	nos.		
15	curtain with s.s. pipe & clamp in locker & tijori	1	nos.		
16	A.C.P. work (front column panneling & Front Board,Side & Celling)	438.9	sq.ft.		
17	Havy m.s.safty grill	0	sq.ft.		
18	Havy 20 Gauge Collupsible 1 Nos.	110	sq.ft.		
19	Oil paint on all Febrication Work at site lum sum	925	sq.ft.		
20	lum sum provision of old furniture ,floorig & celling etc				
	TOTAL				

dev
Consultant Engineer & Interior Designing
B/501/2, Tirupati Plaza, Near Collector Office, Nanpura, Surat-395001 Gujarat, India.
Mo. : (o) +91-99099-06885
Email .: devarch19@ gmail.com.

Name Of Work : ATM Furniture Work of surat districtco.op.bank ltd. @ Rander branch,Dist.Surat.
Name Of Owner : The Surat District Co-Operative Bank, majura gate, Surat.

ATM WORK

(B) (1)

Sr.No.	Description	Qty	Per	Rate	Amount
1	Making & Fixing 12mm tonghned glass partation with				
	necessory fixtures at main entery like patches ,handle etc.	24	sq.ft.		
2	Pro.& Fix Floor Spring	1	nos		
3	Making & Fixing MS battery Stand				
	Size : 2'-6" (L) X 1'-6" (D) X 2'-6" (H)	1	nos		
4	Door with glass	24	sq.ft.		
1	Providing & Fixing Door without glass IN A.T.M.	17.5	sq.ft.		
5	Providing & Fixing Partition without glass IN A.T.M.	35	sq.ft.		
6	Providing & Fixing venyle logo on door	2	nos		
7	Gypsum False Ceiling	48.75	sq.ft.		
8	Wall P.O.P	100	sq.ft.		
9	Box Type sign board for ATM	1	nos		
10	WALL COLOUR	100	sq.ft.		
11	CEILING COLOUR	0	sq.ft.		
12	Acp work (front column penneling & Celling)	185	sq.ft.		
	TOTAL B (1)				

ATM ROOM (ELECTRIC)

B (2)

Sr.No.	Description	Qty	Per	Rate	Amount
1	Light point	4	nos.		
2	5A Plug Point	3	nos.		
3	15A Plug Point	3	nos.		
4	Main 1.5 mm	25	r.mt.		
5	Main 2.5 mm	30	r.mt.		
6	Data Cable	85	r.mt.		
7	Data 1/0	2	nos.		
8	Wall Fan	1	nos.		
9	Board Point with Timer	1	nos.		
10	ElecB 32A	1	nos.		
11	DP 32 A	4	nos.		
12	AC Starter	1	nos.		
13	Load Setting	1	nos.		
14	18 W Led (Light)	4	nos.		
15	T-5 (Tublight)	1	nos.		
16	Earthing Point (With Coper Plate)	1	nos.		
17	Timer Board Point With Analog Timer	1	nos.		
18	ATM DB with 4 WSPN & 25 A MCB	1	nos.		
19	camera cable	90	r.mt.		
20	CCTV points & Camera	3	nos.		
21	6sq.mm Main Liin	25	r.mt.		
	TOTAL B (2)				
	TOTAL (B) = B (1) + B (2)				

	A	B	C	D	E	F
1	Dev					
2	Consultant Engineer & Interior Designing					
3	B/501/2, Tirupati Plaza, Near Collector Office, Nanpura, Surat-395001 Gujarat, India.					
4	Mo. : (o) +91-99099-06885					
5	Email .: devarch19@ gmail.com.					
6						
7	Name Of Work : Electric Work of surat districtco.op.bank ltd. @ Rander branch,Dist.Surat.					
8	Name Of Owner : The Surat District Co-Operative Bank, majura gate, Surat.					
9						
10	(3) OFFICE ELECTRIC WORK					
11	Sr.No.	Description	Qty.	Unit	Rate	Amount (INR)
12						
13	1	12 Way SPN DB : (CPDB) MCB elec.pannels				
14		Incoming : 40 A FP ELMCB / RCCB - 100 mA				
15		Outgoing : 6 to 20 A SP MCB (10 nos.)	0	nos.		
16	*	Supply & Installation of 20A/25A SP MCB AC DB	0	nos.		
17	*	Supply & Installation of 40A/63A DP MCB with MS	0	nos.		
18		Enclosure for UPS DB				
19	*	Supply & Installation of 40A/63A DP MCB with MS	0	nos.		
20		Enclosure for UPS DB with 12 W SP & DB & 10 nos				
21		25A SP MCB	1	nos.		
22	*	Supply & Installation of 8 way ETPN Double door DB	0	nos.		
23		1 # 80 AMP MCB,32 AMP DP MCB 3 no & 16/20/32				
24		AMP SP MCB	0	nos.		
25						
26	2	INTERNAL WIRING				
27	a	Providing and making point wiring in concealed in				
28		walls, furnitures and for above false ceiling, or on				
29		ceiling, on beams shall be fixed with saddles and				
30		spacers etc., with conduits taken in slab/walls/				
31		furnitures with 20 mm dia P.V.C. Rigid conduits 1.5				
32		mm thick/1.8 mm thick for 25 mm ISI mark with				
33		bends, tees, elbows etc. with 650/1100 V grade ISI				
34		marked PVC insulated Finolex or R.R.copper				
35		conductor wires , including circuit mains from DB to				
36		SB and SB to SB of 2 x 2.5 + 1.5 sqmm PVC				
37		insulated copper conductor wires and point wiring of				
38		3 Nos. of 1.5 sq multi-stranded flexible type PVC				
39		insulated copper conductor wires all accessories				
40		screws and washers M.K India make wraparound				
41		series / Clipsal Opal / North west screwless make /				
42		Anchor make Woods series with its modular cover				
43		plate, switches, fan regulators, 6 amp plugs, flush				
44						
45		metal box or surface PVC box or flush PVC box for				

	A	B	C	D	E	F
46		trucking system etc. of company made and outlet				
47		boxes of 18 SWG red oxide painted, its accessories,				
48		angle holder / batten holder / ceiling rose, etc.,				
49		electrical point to be complete in all respect to the				
50		satisfaction of E.I.C				
51	b	One 6 A switch controlling one light point	37	pts		
52	c	One 6A switch controlling one fan point with fan hook				
53		and M.K India make wraparound series / Clipsal Opal				
54		/ North west screwless make / Anchor make Woods				
55		series step control type fan regulators etc., complete	4	pts		
56	d	6A socket outlet (5 pin) with 6A SP switch (on				
57		common board).	10	nos.		
58	e	6A socket outlet (5 pin) with 6A SP switch (as an				
59		independent point) .	10	nos.		
60	f	Call bell point with supply of bell push complete	1	nos.		
61	3	-do-as item above but for 20 A (5 pin) switch socket				
62		with modular box duly concealed of M.K India make				
63		wraparound series / Clipsal Opal / North west				
64		screwless make / Anchor make Woods series to the				
65		satisfaction of E.I.C	2	nos.		
67	4	2 nos. of 2.5 sq mm wires and 1 no. of 1.0 sq mm				
68		PVC Insulated copper conductor wires	150	rmt		
69	5	2nos. of 4.0 sq mm wires and 1 no. of 1.5 sq mm				
70		PVC Insulated copper conductor wires	120	rmt		
71	6	TELEPHONE AND STRUCTURED CABLING :				
72	a	Supply and installing telephone point with Telephone				
73		socket outlets of RJ 11 of M.K India make wraparound				
74		series / North west make / Clipsal Opal make series				
75		and concealed boxes in walls / furnitures etc				
76		complete all respect to the satisfaction of E.I.C Also				
77		provinding, drawing and laying of PVC Rigid Conduit				
78		20mm dia 1.5 mm thick , telephone wires of 2 pair				
79		0.51 cross section copper tinned PVC insulated				
80		telephone wire of ITI approved etc with necessary				
81		terminations, ferrule numbering etc. complete.	4	nos.		
82	b	CAT 5 telephoneline	255	r.mt.		

	A	B	C	D	E	F
83	7	COMPUTER POWER SUPPLY SYSTEM.				
84		Supply and installation of 2 nos. of 6 A, 5 pin				
85		Sockets and 1 no. of 16 A Socket outlets with one 16				
86		A switches with indicator all of M.K India make				
87		wraparound series / Clipsal Opal / North west				
88		screwless make / Anchor make Woods series				
89		Computer power supply with concealed metallic				
90		boxes or PVC box for surface of company made etc				
91		complete all respect to the satisfaction of E.I.C.				
92		Including with 20 mm dia P.V.C. Rigid conduits				
93		1.5 mm thick ISI mark with bends, tees, elbows etc.				
94		with 650/1100 V grade ISI marked PVC insulated				
95		copper conductor wires , including circuit mainns				
96		from DB to SB and SB to SB of 2 x 2.5 + 1.5 sq.mm.				
97		PVC insulated copper conductor wires.				
98		CONSIDER ONE CIRCUIT FOR EVERY 3				
99		POINTS ie LOOPED UP TO 3 POINTS.				
100	a	computer point	5	nos.		
101	b	computer line with cad6 wire D-link / Molex / R.R. with				
102		p.v.c. condute	35	r.mt.		
103	8	FAN				
104		Supply, Installation, Testing & Commissioning of				
105		Lighting fixture / fans / Exhust fan with inclusive of				
106		flexible wires, adaptor etc. coplete with all required				
107		hard wares etc.complete to the requirement and the				
108		satisfaction of E.I.C.				
109	a	Ceiling Fan Suppling, erecting, testing and				
110		commissioning of high speed 48" (1200 mm sweep)				
111		double ball bearing ceiling fan with condenser A.C.				
112		230V, 50cycles with canopy, down rod upto 300 mm				
113		length with rubber bushing, bolts & nuts in the				
114		provided fan hook box of required size complete				
115		erected.Crompton / hevels /bajaj make cool breeze,				
116		white 48" or equivalent	4	nos.		
117	b	6" Exusfan	0	nos.		
118	c	wall fan	1	nos.		
119	9	Light fixture				
120	a	Supply, Installation, testing & commissioning of LED				
121		18 V pennel.	30	nos.		
122	b	Supply, Installation, testing & commissioning of LED				
123		T5 light fixture.	1	nos.		
124	10	C.C.TV Cemera Syastem				
125	a	CAD 6 d-link insulated & sheathed cable in 20 / 25				
126		MM dia Rigind PVC Conduit.	285	r.mt.		
127	b	C.C.TV. Points	7	nos.		
128	c	C.C.TV. Camera	7	nos.		

	A	B	C	D	E	F
130	11	CABLES & CABLE TERMINATIONS :				
131	1	Supplying & Laying PVC armored cable of 1100 V				
132		grade of copper / conductor (as required) of following				
133		sizes in ready made trench mounted on wall with				
134		identification lugs at both ends, digging of trench				
135		prelaid RCC hume pipe with necessary cable				
136		identification lugs at both ends, digging of trench and				
137		its filling with second class bricks, send the cable				
138		shall ISI mark and confirming to latest ISS. All the				
139		cable shall be terminated with suitable sizes of luga.				
140	a	1 core 10 sq.mm. copper flexible cable (for UPS				
141		Input / Output)	30	r.mt.		
142	b	4 core 6 sq.mm. copper cable (Panel to UPS				
143		supply & Meter to D.B)		r.mt.		
144	c	4 core 25 sq.mm. copper cable (Meter to D.B.)		r.mt.		
145	d	4 core 50 sq.mm. Aluminium armoured cable				
146		(Meter to Panel)	0	r.mt.		
147	e	4 core 1.5 sq.mm. copper cable Penic Switch				
148		cables	35	r.mt.		
150	12	CHEMICAL EARTHING :				
151	1	Providing & Erection earthing as per drawing				
152		complete with 450mm X 450mm X 3mm thk.				
153		Copper earth plate with following size of copper.				
154		Earthing strip at the technically respective				
155		position with digging of earth & refilling with				
156		charcoal & salt complete with masonary enclour				
157		made of cast iron cover plate having lockable				
158		arrangement & watering pipe &guide pipe of				
159		suitable size of earth pit. Job include supply and				
160		suitable size of earth pit. Job include supply and				
161		laying of CU strip of 25 X 3mm thick with proper				
162		saddeling with minimum distance at 1.5 feet.	0	nos.		
163	2	1 SINGLE CORE 10 MM COPPER WIRE	0	r.mt.		
164						

	A	B	C	D	E	F
165	13	63 A 3Phase Change Order	0	nos.		
166	14	Security Cable Loading Condit	240	r.mt.		
167	15	Timer Board Point With Analog Timer	1	nos.		
168	16	30W Flood Light Fitting at Outside Board With Clamps	7	nos.		
169	17	1.0 sq.mm 1 phase main for generator	47	r.mt.		
170	18	63 A MCCB at AC DB with box	1	nos.		
171	19	Branch board point with timer	1	nos.		
172	20	12 w LED surface Fixture at Cash ounter	0	0		
173	21	Security system wire	240	r.mt.		
174	22	1.00 sqmm. Main line for genretor	50	r.mt.		
175	23	pro. & fix 30 W LED Flood light	7	nos.		
176	24	pro.& fix.100 A fuse	3	nos.		
177	25	pro.& fix. 3 ∅ MCCB 100A with box at meter	1	nos.		
178	26	pro.& fix. 3 ∅ MCCB 100A with box at AC DB	1	nos.		
179	27	16 sqmm flexi.load main	10	r.mt.		
180	28	6 sqmm flexi.load main	10	r.mt.		
181	29	10 sqmm flexi.load main	10	r.mt.		
182	30	1.5 sqmm main line	272	rmt.		
183	31	pro. & fix. 9 U rack for data main	0	0		
184	32	provision of temerory electric work lum sum	0	0		
185	TOTAL					
186						

dev
Consultant Engineer & Interior Designing
B/501/2, Tirupati Plaza, Near Collector Office, Nanpura, Surat-395001 Gujarat, India.
Mo. : (o) +91-99099-06885
Email .: devarch19@ gmail.com.

Name Of Work : Air Conditioner Work of surat district co.op. bank ltd. @ Rander Branch, Dist Surat.
Name Of Owner : The Surat District Co-Operative Bank, majura gate, Surat.

(4) OFFICE AIR CONDITIONER WORK

Sr.No	Description	Qty.	Unit	Rate	Amount (INR)
1	Providing Mitsubishi Make 1.95 Ton 5-star Rated Split Air Condiutioner with All Taxes & All Need Copper Piping / Thermal Insulation Installation.	0	0		
2	Providing Mitsubishi Make 1.60 Ton 5-star Rated Split Air Condiutioner with All Taxes & All Need Copper Piping / Thermal Insulation Installation.	2	nos.		
2	conshield drain pipe work		lump-sum		
	OFFICE AIR CONDITIONER WORK			(A)	

ATM AIR CONDITIONER WORK

Sr.No	Description	Qty.	Unit	Rate	Amount (INR)
1	Providing Mitsubishi/ Voltas or equivalent Make 1.0 Ton 5-star Rated Split Air Condiutioner Re-Fitting with All Taxes & All Need Copper Piping / Thermal Insulation Installation	1	nos.		
2	conshield drain pipe work		lump-sum		
	ATM AIR CONDITIONER WORK			(B)	
				(A + B)	